N

NORTHERN ROUNDABOUT

SOUTHERN ROUNDABOUT

Gantrys

Track

Def

Tunnels

Pond

Bdy

P0

P02c

P07a

AOS

PROPOSED GABIONS

TREES TO BE REMOVED

PROPOSED REED BED

MANHOLE TO BE RELOCATED

LAMP POST TO BE RELOCATED

TREES TO BE REMOVED

RELOCATED TRAFFIC SIGN

TREES TO BE REMOVED

SIGNALIZED STAGGERED CROSSING

GULLY TO BE RELOCATED

ROAD SIGN TO BE RELOCATED

GULLY TO BE RELOCATED

INSPECTION CHAMBER TO BE RELOCATED

GULLY TO BE RELOCATED

LINE OF TREES TO BE REMOVED

MANHOLES TO BE RELOCATED

GULLY TO BE RELOCATED

BUS ONLY

LIME TREE AVENUE

GULLY TO BE RELOCATED

LAMP POST TO BE RELOCATED

SPL TO BE RELOCATED

ROAD SIGNS TO BE RELOCATED

TUNNEL WESTERN PORTAL

NEW TUNNEL

NEW TUNNEL

TUNNEL EASTERN PORTAL

TREES TO BE REMOVED

ROAD SIGN TO BE RELOCATED

GULLY TO BE RELOCATED

TREES TO BE REMOVED

PROPOSED 800mm DIAG. PIPES

EXISTING TUNNELS

WEST AND EAST CLIFF FACES TO BE STABILIZED

MAINTENANCE PARKING AREA

70.28

1:500 METRIC

5m 0 5m 10m 15m 20m

This drawing includes asp data licensed from ordnance survey
(C) Crown copyright and database rights 2019
OS 100025229

NOTES

1. Drawing to be printed in colour.
2. Do not scale from drawing.
3. All dimensions are in metres unless stated otherwise.

KEY

- Proposed Road Markings
- Proposed Traffic Signal
- Proposed Traffic Sign
- Proposed bollard
- Proposed kerb
- Proposed splay kerb
- Proposed edging
- Proposed footpath pavement
- Proposed carriageway pavement
- Existing kerb to be removed
- Proposed HFS
- Existing water course and ponds area
- Existing Reed bed
- Proposed verge
- Proposed maintenance parking area
- Proposed pedestrian fence
- Proposed gabions
- Proposed reed bed
- Proposed tactile paving
- EQ Countryside Clarion parcel plan

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION

In addition to the hazards/risks normally associated with the types of work detailed on this drawing, note the following :

CONSTRUCTION
A000 - Identify and locate existing services
All buried services to be isolated / protected prior to start of works

MAINTENANCE / CLEANING
- As above

DECOMMISSIONING / DEMOLITION
- As above

It is assumed that all works will be carried out by a competent contract or working, where appropriate, to an approved method statement

Rev	Rev. Date	Purpose of revision	Drawn	Checkd	Rev'd	Apprv'd
P02	JUNE. 2019	TOPO SURVEY UPDATED	CP	MJ	SY	PW
P01	MAY. 2019	FOR CONSULTATION	CP	MJ	SY	PW

Client: Kent County Council

Project: Fastrack Full Network
Bean Road Tunnel

Drawing title:

REFERENCE DESIGN GENERAL ARRANGEMENT PLAN

Drawing status: FOR CONSULTATION

Scale	1:500 @ A1	DO NOT SCALE
Jacobs No.	B2350500	Rev P02
Client no.		

Drawing number: B2350500-JAC-HA-XX-DR-D-0001

© Copyright 2018 Jacobs U.K. Limited. The concepts and information contained in this document are the property of Jacobs. Use or copying of this document in whole or in part without the written permission of Jacobs constitutes an infringement of copyright. Limitation: This drawing has been prepared on behalf of and for the exclusive use of Jacobs' Client, and is subject to, and issued in accordance with the provisions of the contract between Jacobs and the Client. Jacobs accepts no liability or responsibility whatsoever for, or in respect of, any use of, or reliance upon, this drawing by any third party.

\\Lonfpp02\Proj\TTIJ Projects\Bean Road Tunnel\Design - Drawings\CAD\Highways\GEN\B2350500-JAC-HA-XX-DR-D-0001_GA-Option 5_1FILE.dwg - 20/06/2019 13:48:43 - CONB - PopsC